5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which his tender will be cancelled and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

Abstract estimate of quantities for restoring Bannur Urubagalkere (Kengattekere Reg. No. 185 Sorab Taluk).

No.	Items of work	Per	Quantity
	Bund at R. L. 56·00 Top width 4½'		
1	Jungle clearing and cutting grips, etc., complete ...	Lumpsum	
2	Earthwork for bund including watering tamping complete	C.yd.	4,559
3	Turfing the front and rear slopes of bund	Sqr.	303·06
4	Providing and fixing grade stones on a concrete bed of 1'x1'x1' including figuring and painting, etc., complete.	Each	13
	Do do top width stones ...	,,	13
	Do do Reg. No. and date stones	No.	1
	Do do B. M. stones ...	Each	2
	Constructing a pipe sluice at C. S. 7 R. L. 47·50.		
1	Cutting open the bund pipe portion only	C.yd.	9
2	Refilling the bund with watering and tamping ...	,,	10
3	Earthwork excavation for foundation	,,	6
4	Concrete in surki mortar	C.ft.	148
5	Size stone in surki mortar	,,	163
6	Burnt stone slabs 6" thick roughly fixed and dressed ...	S.ft.	47
7	Cement concrete coping over head walls	C.ft.	6
8	Pointing in surki mortar	Sq.	3·00
9	Cutting orifice holes ventway and sill stones in slabs ...	Lumpsum	
10	Providing a teakwood plug with iron rod including locking arrangement, etc., complete.	,,	
11	C. I. pipe 8" dia. with carting and heating joints, etc., complete.	R.ft.	24
	Weir in the left flank length 12 feet R. L. 52·00.		
1	Earthwork excavation foundation	C.yd.	21
2	Concrete in surki mortar	C.ft.	101
3	Size stone in surki mortar	,,	128
4	Pointing in surki mortar	Sq.	3·00
5	Cement concrete coping and plastered over	C.ft.	19
6	Rough stone work	C.yd.	21

R. H. STEELE,
Executive Engineer.

OFFICE OF THE EXECUTIVE ENGINEER, DAM CONSTRUCTION AND NO. I CANAL DIVISION, KRISHNARAJASAGARA.

Notice dated 30th June 1930.

The public are hereby informed that the undermentioned unserviceable articles will be sold by auction at the P. W. Store yard commencing at 10 A.M. on the 27th July 1930 and on the following day if necessary.

The highest bidder will be the purchaser. But if proper bids are not forthcoming, the article will not be knocked down. The purchase value of the article should be paid immediately after the sale is effected and the articles removed. Otherwise, the articles sold, will be at the risk of the purchaser.

Statement of Unserviceable Tools and Plant articles available for sale as Scrap.

No.	Particulars	
	Tools.	
1	Adges	2
2	Anvils each 2 cwts.	2
3	Augers of sizes	199
4	Axes pick	78
5	Axes felling	114
6	Bill hooks	7
7	Crow bars steel and iron	488
8	Pulleys differential 10 tons	1
9	Do do 2 ,,	1
10	Do do 1 ,,	1
11	Do do 5 ,,	3
12	Pulleys double shieved	1
13	Do treble do	1
14	Butt hammers	40
15	Hammers ordinary	24
16	Do revetters	3
17	Do spiking	9
18	Do 1½ lbs. sledge	1
19	Do 1 ,, do	1
20	Do 3 ,, do	17
21	Do 4 ,, do	23
22	Do 6 ,, do	12
23	Do 7 ,, do	2
24	Do 10 ,, do	23
25	Jim crow	2
26	Mamaties	245
27	Pans mortar iron	202
28	Pliers cutting	3
29	Do gas	1
30	Pick beaters	12
31	Pots iron for water	19
32	Tampers cast iron round	2
33	Tank iron and galvanised	2
34	Tongs lifting flat and round	13
35	Spanners of sizes	60
36	Hand dhollies	16
37	Wells lights	4
38	Spare dies	5
39	Sand boxes	4
40	Moulds brick iron	21

No.	Particulars	
	Machinery.	
1	Teaming trolley	1
2	Blowers	1
3	Crabwinches	2
4	Mills for mortar grinding	7
5	Do 8 feet	7
6	Do 9 feet	1
7	Machine hand drilling with and without bits	7
8	Machine hand screwing with bits	1
9	Vaperizer of Rational Oil Engine	1
10	Machine hand dressing	2
	Ferry.	
1	Iron cooly barge 60' x 12'—6" x 1' x 6"	1
	Materials.	
1	Iron scrapers big and small	20
2	Boring rods	88
3	Masons crow bars	144
4	Chisles	3
5	Butt hammer bits	116
6	Wedges steal	112
	Truck and Tramway Materials.	
1	Trucks spare wheels	26
2	Wheels on axles inside bearing	3
3	Wheels on axles outside bearing	1
4	Girder trolleys	10
5	Wooden trolleys	5
6	Spire shaft	1
7	Iron drums	2
	Mortar Mills Parts.	
1	Pinion cog wheel	1
2	Shafting rollers of mortar mills	1
3	Fast and loose pulleys	1

N. SARABHOJA,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS.

OFFICE OF THE INSPECTOR-GENERAL OF POLICE IN MYSORE, BANGALORE.

Notification dated 2nd July 1930.

Sealed tenders will be received at the Office of the Inspector-General of Police in Mysore, Bangalore, for the supply of the undermentioned articles and for the making up of clothing for the use of the Mysore Police according to approved samples, which will be open for inspection, in the Central Stores on any working day during office hours. The samples will on no account be furnished.